

Operations Committee Meeting Tuesday, February 2, 2021 at 1:00 PM Valley Sanitary District Board Room 45-500 Van Buren Street, Indio, CA 92201

*****SPECIAL NOTICE – VIA VIDEOCONFERENCE*****

Pursuant to the Governor's Executive Order N-25-20 issued March 4, 2020 and N-29-20 issued on March 18, 2020 the Operations Committee regular meeting will be conducted remotely through Zoom. Members of the public wanting to participate in the open session of the meeting may do so vis the following Zoom registration link: <u>https://zoom.us/j/99992916216?pwd=Z1p2VEFMNUhsSlVGYzRDZ1ZBL3poZz09</u> Meeting ID: 999 9291 6216 or by telephone 669-900-9128.

Members of the public wanting to address the Committee, either during public comment or for a specific agenda item, or both, are requested to send an email notification no later than 12:30 p.m. on the day of the meeting to the Valley Sanitary District's Clerk of the Board at hgould@valley-sanitary.org.

Page

1. CALL TO ORDER

- 1.1. Roll Call
- 1.2. Pledge of Allegiance

2. PUBLIC COMMENT

This is the time set aside for public comment on any item not appearing on the agenda. Please notify the Secretary in advance of the meeting if you wish to speak on a non-hearing item.

3. DISCUSSION / ACTION ITEMS

3.1.	Collection System Rehabilitation and Replacement Project Update	3 - 21
	3.1 Collection System Rehabilitation & Replacement Project.pdf 🖉	
	3.1 Attachment A - Board Presentation v5 012721.pdf 🖉	
3.2.	Influent Pump Station Rehabilitation Project Update	22 - 23
	3.2 Influent Pump Station Rehabilitation Project.pdf 🔗	
	3.2 Attachment A - Bypass Plan.pdf 🖉	
3.3.	Reclaimed Water Project - Phase 1 Update	24 - 26
	3.3 Reclaimed Water Project - Phase I.pdf 🖉	
	3.3 Attachement A - BODR Site Plan.pdf 🖉	

4. FUTURE MEETING ITEMS

5. ADJOURNMENT

Pursuant to the Brown Act, items may not be added to this agenda unless the Secretary to the Board has at least 72 hours advance notice prior to the time and date posted on this notice.





Valley Sanitary District Operations Committee February 2, 2021

TO:	Operations Committee
TO:	Operations Committee

FROM: Ron Buchwald, Engineering Services Manager

SUBJECT: Project Update: Collection System Rehabilitation & Replacement Project

□Board Action	□New Budget Approval	□Contract Award
⊠Board Information	□Existing FY Approved Budget	□Closed Session

Executive Summary

The purpose of this report is to provide a project update and information regarding VSD's Collection System Rehabilitation and Replacement Project. A PowerPoint presentation will be provided.

Strategic Plan Compliance

This item complies with VSD Strategic Plan Objective 3: Excellent Facilities.

Fiscal Impact

The current fiscal year impact of this project is \$2,643,928 million as shown in the CIP budget. The total estimated construction cost of this project is \$57,520,000 to be spent over the next ten years. In total, this is a substantial and significant project and one of VSD's largest.

Background

This project began in early 2018 and at that time was intended to be a 10-year project. This project has started slower than anticipated for several reasons. We have built a strong foundational program that we can build on over the next 10 years. We have also built a good team with the consultant. We are now just getting some smaller projects out for construction to get a better feel on how to continue to move forward with larger projects. We are also working through some difficult, challenging issues now so that we can tackle them in the future.

Recommendation

To continue to fund this important project by raising sewer rates and acquiring debt.

Attachments

Attachment A: PowerPoint presentation



VALLEY SANITARY DISTRICT COLLECTION SYSTEM INFRASTRUCTURE PROJECT

Board Operation Committee February 2, 2021

AGENDA

- Program Background
- Total Program Costs
- Expenditures by Year
- Collection System by the Numbers
- Sewer Pipeline Condition
- Major Components of the Program
- Capital Improvement Projects
- Tracking Program Success



PROGRAM BACKGROUND

Collection System Infrastructure Project Objectives:

- Maintain excellence of service to rate payers
- Maintaining a high standard of operations and maintenance
- Forward thinking in planning for facility and operational needs
- Achieving cost efficiency and effectiveness





TOTAL PROGRAM COSTS

PLANNING OPINION OF PROBABALE CONSTRUCTION COSTS January 25, 2021

VALLEY SANITARY DISTRICT SEWER IMPROVEMENT SUMMARY OF COSTS

LOCATED IN CITY OF INDIO, CALIFORNIA

12 YEAR PROGRAM COST

Item	Item Description	LF		Item Total	
1	Rehabilitation of Sewer Mains and Manholes (CIPP)	65,990		\$9,810,34	
2	Point Repair	1,380		\$933,81	
3	Realignment	18,389		\$13,728,55	
4	Replacement In Place Sewer Mains and Manholes	11,125			
5	Budgeted Not Yet CCTV'd / Assumed Repairs For Sewer Mains Not Inspected	20,127		\$8,052,93	
6	Replace In Place Sewer Manholes Outside of Improvement of Mains	25		\$393,00	
7	Inspections By Outside Forces	37,306		\$265,61	
ub-To	tal Construction Costs			\$37,759,86	
ub-To	Soft Costs:				
ub-To	Soft Costs: Project Management (6%)		\$	2,265,59	
ub-To	Soft Costs: Project Management (6%) Design / Survey / Geotech / Misc. (109		\$	2,265,59 3,775,98	
ub-To	Soft Costs: Project Management (6%)			2,265,59 3,775,98	
	Soft Costs: Project Management (6%) Design / Survey / Geotech / Misc. (109		\$	2,265,59 3,775,98 3,775,98	
	Soft Costs: Project Management (6%) Design / Survey / Geotech / Misc. (10 ⁶ CM / Inspection / Material Testing (10 ⁶		\$		

Harris & Associates

EXPENDITURES BY YEAR

Const 3

Progm 4

Const 1

Progm 2

Progm 1

Const 2

Progm 3

Year	2019/20	2020/21	2021/22	2022/23	2023/24	2024/25	2025/26	2026/27	2027/28	2028/29	2029/30	2030/31	
					C	onstruction							
	0.00%	1.40%	5.83%	10.3%	12.9%	15.4%	15.4%	12.9%	10.3%	7.8%	5.2%	2.7%	
					Progra	m Delivery	Cost						
	2.56%	4.02%	7.13%	12.57%	15.01%	15.01%	12.57%	10.13%	7.69%	5.25%	5.25%	2.81%	
													Total
Budgeted Annual Construction Cost	\$529,510	\$1,809,854	\$2,200,000	\$3,892,190	\$4,853,740	\$5,815,280	\$5,815,280	\$4,853,740	\$3,892,190	\$2,930,650	\$1,969,100	\$1,007,560	\$37,759,868
Annual Escalation Construction Cost	\$0			\$405,663	\$685,963	\$1,044,862	\$1,275,363	\$1,263,338	\$1,177,881	\$1,015,163	\$771,166	\$441,707	\$8,081,107
Forecasted Construction Cost	\$0	\$530,138	\$2,200,000										
Budgeted Annual Program Soft Cost	\$451,900	\$834,074	\$700,000	\$1,233,980	\$1,473,430	\$1,473,430	\$1,233,980	\$994,530	\$755,070	\$515,620	\$515,620	\$276,170	\$9,817,570
Annual Escalation Program Soft Cost	\$0			\$128,611	\$208,235	\$264,739	\$270,627	\$258,858	\$228,504	\$178,608	\$201,934	\$121,071	\$1,861,188
Actual Program Soft Cost	\$251,002	\$152,056											
Projected Program Soft Cost	\$0	\$242,682	\$700,000										
Total Annual Budgeted Cost	\$981,410	\$2,643,928	\$2,900,000	\$5,660,444	\$7,221,368	\$8,598,311	\$8,595,250	\$7,370,466	\$6,053,645	\$4,640,041	\$3,457,821	\$1,846,508	\$57,519,734
Total Program Cost (Actual + Projected)	\$251,002	\$924,876	\$2,900,000										

VSD 12 Year Program - Forcasted Expenses By Year

Const 5

Progm 6

Const 6

Progm 7

Const 7

Progm 8

Const 8

Progm 9

Const 9

Progm 10

Const 10

Progm 12


Const 11

Progm 12

Const 4

Progm 5

VSD



COLLECTION SYSTEM BY THE NUMBERS

COLLECTION SYSTEM INVENTORY:

- Sewer Pipeline 1,332,487 Linear feet
- Manholes 4,910 each

COLLECTION SYSTEM AGE							
Pipe Age	Current % of System	In 5 years	In 10 years				
50-75 years	<mark>24%</mark> (Prior to 1971) (1.7% over 75-yr)	<mark>27%</mark> (Prior to 1976)	<mark>37%</mark> (Prior to 1981)				
50 years to 25 years	<mark>32%</mark> (1971 to 1996)	<mark>37%</mark> (1976 to 2001)	<mark>63%</mark> (1981 to 2006)				

Typical Lifespan of Sewer

- Clay pipe: 75+ years (maintenance much higher due to its brittle nature)
- PVC pipe: 100 years before requiring replacement
- Cured-In-Place-Liner: 50+ years and perform as well or better than original sewer piping materials



Page 9 of 26

MAJOR COMPONENTS OF THE PROGRAM

- INSPECTION
- ASSESSMENT
- PRIORITIZATION
- DESIGN
- CONSTRUCTION



INSPECTION (10-year cycle)

- CCTV'd Sewer Pipeline 1,095,948 linear feet (82%) (2008-2020)
 - Inspect approximately 120,000 lineal feet per year
- Non-CCTV'd Sewer Pipeline 236,539 linear feet (18%)







INSPECTION SEWER PIPELINE CONDITION

Sewer Pipeline (QRS) Grading CCTV Table*

Quick Rating Structural (QRS) Grading	Linear Foot of VSD CCTV'd Sewer Pipeline (LF)*	Percentage of VSD Sewer Pipeline Inspected
5	17,402	1.4%
4	71,277	5.3%
3	61,912	4.6%
1/2	219,335	16.5%
No Defect found	726,022	54.4%
Pending Values	236,539	17.8%
Total=	1,332,487	100.0%

QRS Rating

- 5 Most significant defect grade
- 4 Significant defect grade
- 3 Moderate defect grade
- 2 Minor to moderate defect grade
- 1 Minor defect grade



INSPECTION MANHOLE CONDITION





ASSESSMENT

Proposed Rehabilitation Methods


- Point Repair
- Cured In Place Pipe
- Realignment of sewer mains
- Replacement of sewer mains in place
- Manhole rehabilitation



Pipe Bursting














CAPITAL IMPROVEMENT PROJECTS








VSD



TRACKING PROGRAM SUCCESS











THANK YOU

Valley Sanitary District





Valley Sanitary District Operations Committee February 2, 2021

TO:	Operations Committee
10.	oporationo committeo

FROM: Ron Buchwald, Engineering Services Manager

SUBJECT: Project Update: Influent Pump Station Rehabilitation Project

□Board Action	□New Budget Approval	□Contract Award
⊠Board Information	□Existing FY Approved Budget	□Closed Session

Executive Summary

The purpose of this report is to provide a project update and information regarding VSD's Influent Pump Station Rehabilitation Project.

Strategic Plan Compliance

This item complies with VSD Strategic Plan Objective 3: Excellent Facilities.

Fiscal Impact

The current fiscal year impact of this project is \$1.2 million as shown in the CIP budget. This should produce 60% design plans and a guaranteed maximum price (GMP) to construct. The total estimate price is \$2,600,000.

Background

The influent pump station is showing significant signs of deterioration. Internal piping is losing their protective coating, the coating covering the walls is starting to show signs of failure, and gates sealing each pump bay are leaking. VSD has awarded the Design/Build project to Downing Construction and Dudek Engineering. This project consists of installing sewer main by-pass to fully inspect the influent pump station to determine the necessary repairs. The initial design and construction estimate will then be completed. A final award by the Board will then allow this project to continue to construction. The repairs are necessary to keep the influent pump station working properly. Postponing the repairs will cause permanent damage to the structure and/or cause a complete failure of the pump station.

Recommendation

To continue to fund this important project.

Attachments

Attachment A: By-pass plan diagram




Exhibit: Valley Sanitation District IPS Design Build Rehab Project - Bypass Plan





Valley Sanitary District Operations Committee February 2, 2021

TO:	Operations Committee
FROM:	Ron Buchwald, Engineering Services Manager

SUBJECT: Project Update: Reclaimed Water Project – Phase I

□Board Action	□New Budget Approval	□Contract Award
⊠Board Information	□Existing FY Approved Budget	□Closed Session

Executive Summary

The purpose of this report is to provide a project update and information regarding VSD's Reclaimed Water Project Phase I.

Strategic Plan Compliance

This item complies with VSD Strategic Plan Objective 3: Excellent Facilities.

Fiscal Impact

The current fiscal impact of this project is \$2.2 million which will produce 60% design plans. In fiscal year 2021/22, Staff will request from the Board the authorization to award the completion of design and construction of this project estimated to be about \$46 to \$50 million.

Background

The Reclaimed Water Project Phase I is the initial project of three phases that will allow VSD to be able to produce reclaimed water. This is a significant project that will replace and improve some treatment structures and provide redundancy for other treatment structures so that we can eventually decommission the ponds (Phase II) which will provide the needed area to construct additional treatment systems to meet upcoming regulatory requirements and to be able to produce reclaimed water (Phase III). Phase I is expected to be completed by early 2025.

Staff, along with the Design/Build team, have made progress towards the 30% design milestone. The team has determined ways to save money by eliminating the sludge holding tank by using the second digester as a holding tank. However, we have also determined that we will need to retain the north cell (pond) and build a small pump station in order to treat the effluent from the belt filter press which is high in ammonia.

Operation staff have been significantly involved in this project which has provided tremendous value in creating a well thought out initial design (they are part of the

reason that a sludge holding tank was determined to be not needed). However, this has also created a burden on staff as they need to find time to be involved in this project as well as do their everyday job duties.

Recommendation

To continue to fund this important project by raising sewer rates and acquiring debt.

Attachments

Attachment A: 30% Site plan showing existing and proposed facilities

